

The Illinois State Toll Highway Authority  
 Contract No. X-XX-XXXX  
 I-355/I-55 Noise Abatement Wall  
 Estimate of Probable Cost

EXHIBIT C  
 WOOD

Item No.	Description	Unit	QUANTITY	Unit Price	Cost
203U	ROADWAY EXCAVATION UNCOMMON	CY	237	\$ 50.00	\$ 11,850.00
* 211A	AGGREGATE SUBGRADE (4 in.)	CY	95	\$ 25.00	\$ 2,375.00
* 215A	EXPLORATION TRENCH, UTILITIES	LF	50	\$ 100.00	\$ 5,000.00
217R	TOPSOIL REPLACEMENT	SY	318	\$ 5.00	\$ 1,590.00
* 402AN50B	IDOT BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N50	TON	179	\$ 90.00	\$ 16,110.00
* 402B1	BITUMINOUS MATERIAL (TACK)	GAL	116	\$ 2.50	\$ 290.00
* 403AN70B	IDOT BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, IL-9.5, MIX D, N70	TON	92	\$ 100.00	\$ 9,200.00
420A	EXCAVATION FOR AGGREGATE SHOULDERS	SY	265	\$ 15.00	\$ 3,975.00
420B	AGGREGATE SHOULDER WITHOUT FILTER FABRIC	TON	225	\$ 31.00	\$ 6,975.00
* 587B	WOOD NOISE ABATEMENT WALL	SF	76,321	\$ 18.00	\$ 1,373,778.00
620A2	SEEDING, CLASS A2	ACRE	0.1	\$ 75,000.00	\$ 7,500.00
625A	EROSION BLANKET, TYPE I	SY	318	\$ 2.00	\$ 636.00
701A	SINGLE RAIL GALVANIZED STEEL PLATE BEAM GUARDRAIL	LF	1,162.5	\$ 25.00	\$ 29,062.50
701E1AS	GUARDRAIL BARRIER TERMINAL, TYPE 1A, SPECIAL	EACH	1	\$ 3,000.00	\$ 3,000.00
702C	GUARDRAIL REMOVAL AND REINSTALLATION - RAIL ELEMENTS	LF	2,567	\$ 15.00	\$ 38,505.00
808	BARRIER DELINEATOR	EACH	39	\$ 6.00	\$ 234.00
818	RIGHT-OF-WAY FENCE REMOVAL	LF	3,730	\$ 5.00	\$ 18,650.00
* 1001	MAINTENANCE OF TRAFFIC	LS	1	\$ 90,000.00	\$ 90,000.00
1001D	PORTABLE CHANGEABLE MESSAGE SIGN, (PER DAY)	EA/DAY	14	\$ 100.00	\$ 1,400.00
1001D1	PORTABLE CHANGEABLE MESSAGE SIGN, (PER WEEK)	EA/WEEK	4	\$ 420.00	\$ 1,680.00
1001D2	PORTABLE CHANGEABLE MESSAGE SIGN, (PER MONTH)	EA/MONTH	2	\$ 1,500.00	\$ 3,000.00
1002	SUPPLEMENTAL MAINTENANCE OF TRAFFIC	DAY	30	\$ 100.00	\$ 3,000.00
1003A	SUPPLEMENTAL BARRICADE	EA/DAY	200	\$ 1.00	\$ 200.00

The Illinois State Toll Highway Authority  
 Contract No. X-XX-XXXX  
 I-355/I-55 Noise Abatement Wall  
 Estimate of Probable Cost

EXHIBIT C  
 WOOD

Item No.	Description	Unit	QUANTITY	Unit Price	Cost
1003B	SUPPLEMENTAL SIGNING	SF	200	\$ 25.00	\$ 5,000.00
1003C	SUPPLEMENTAL FLASHING ARROW BOARD, PER DAY	EA/DAY	7	\$ 35.00	\$ 245.00
1003C1	SUPPLEMENTAL FLASHING ARROW BOARD, PER WEEK	EA/WEEK	1	\$ 200.00	\$ 200.00
1003C2	SUPPLEMENTAL FLASHING ARROW BOARD, PER MONTH	EA/MONTH	1	\$ 500.00	\$ 500.00
* 1006C	DIRECT CONNECT CELL PHONES	EA/MONTH	4	\$ 120.00	\$ 480.00
* 1600A	MOBILIZATION, SPECIAL	LS	1	\$ 105,000.00	\$ 105,000.00
				<b>TOTAL</b>	<b>\$ 1,725,210.50</b>